Abstract estimate for constructing a Hostel for the Veera Saiva Students at Tumkur.

No.	Items of work	Unit	Quantity
	Ground floor—		
1	Earthwork excavation and filling in basement	C. yd.	240
2	Concrete in mortar	C. ft.	2,318
3	Burnt stone in mortar	,,	6,268
4	Burnt stone slabs dressed 6" thick	Sq. ft.	1,584
5	Burnt brick in mortar	C. ft.	7,754
6	Archwork with wire cut bricks in mortar	,,	627
7	Teakwood doors pannelled with iron works, complete	Sq. ft.	56
8	Teakwood battened doors fourfold with expanded metal ventilator at top, complete.	,,	336
9	Teakwood windows pannelled outside and glazed inside with iron bars, iron works complete.	,,	198
10	Teakwood shelves with brass padlock and planks, etc., complete	,,	501
11	Teakwood work with oiling	C. ft.	366
12	Iron girders	Cwt.	17¼
13	Roofing with pakka terrace without flat tiles and plastering	Sqr.	44·51
14	Chunam plastering	,,	130·57
15	White and color washing	,,	130 57
16	Wood oiling	,,	23·86
17	Dental cornice	R. ft.	330½
18	Base and capitals	Each	88
19	Cornice work to arches including key stone	R. ft.	362
20	Ornamental work above arches	L. S.	
21	Cement pointing to basement	Sqr.	6·53
22	Flooring with 1st class Mangalore tiles over 3" concrete bed and cementing	,,	20·64
23	Flooring with 1½" thick Cuddapah slabs on 3" concrete bed and cement pointing.	,,	13·35
24	Providing wooden stair case	Each	2
	First floor—		
1	Burnt brick in mud	C. ft.	9,683
2	Archwork in mortar with wire cut bricks	,,	50
3	Burnt stone slabs 6" dressed	,,	932
4	Teakwood pannelled doors with iron works complete	Sq. ft.	56
5	Teakwood battened doors with expanded metal ventilator at top, etc., complete.	,,	336
6	Teakwood windows pannelled outside, and glazed inside, iron bars, 2" door, iron works, etc., complete.	Sq. ft.	198
7	Teakwood ventilators with glazed shutters, complete	,,	90
8	Do circular, ventilator	,,	14
9	King post truss iron complete	each	2
10	Teakwood shelves with planks, iron works complete	Sq. ft.	504
11	Do work including oiling	C. ft.	326
12	Roofing with 1st class Mangalore tiles over teak reepers, etc., complete	Sqr.	37·06
13	Ornamental ridge tiles set in mortar	R. ft.	136
14	Dwarf wall ornamental at gable ends	,,	100
15	Masonary finials ornamental	Each	4
16	Barge board including finials	,,	4
17	Ornamental eave board	R. ft.	152
18	Ornamental wooden railings	,,	148
19	Cut stone pillars	Each	22
20	Pukka terrace complete	Sqr.	4·96
21	Cornice dental, 2' deep	R. ft.	360
22	Do 1' deep	,,	192
23	Ornamental parapet wall	,,	223
24	Cornice work over arches	,,	78
25	Ornamental work over archways	L. S.	..
26	Cornice work over ventilators	R. ft.	20
27	Do circular ventilators	Each	2
28	False fan light and cornice work over doors and windows	,,	6
29	Flooring with Mangalore tiles and cement pointing	Sqr.	23·24
30	Do Cudapa slabs and cement pointing	,,	16·29
31	Wood oiling	,,	23·86
32	Iron girders	Cwt	35
33	Chunam plastering	Sqr.	195 97
34	White and colour washing	,,	195·97
35	Clearing site and levelling ground	L S.	..
	Kitchen and other works—		
	The plans and estimates are under preparation and will be notified in due course.		

J. RUDRAPPA,
President, Veerashaiva Hostel Committee, Tumkur

OFFICE OF THE DIRECTOR OF INDUSTRIES AND COMMERCE IN MYSORE.

Notification dated 19th April 1923.

Applications are invited from candidates who are desirous of undergoing training in the Government Soap Factory in manufacture of lac and lac products on a stipend of Rs. 15 per month for a period of six months. Two scholarships will be awarded for the purpose. Applications should reach the Director before the 12th May 1923. The candidates should possess sufficient general qualifications.

P. G. D'SOUZA,
Director.